

Techno-Commercial Proposal				REF: TEPL/QTN/12468		Dt: 10.02.2022	
<div>To, Gokul Agro Resources Ltd. Nr.Sharma Resort, Galpadar-Anjar Road, Gandhidham.</div> <div>KA: Mr. Hitesh Prajapati - Purchase Dept.</div>				<div>TRIVENI</div> <div>EQUIPMENTS PVT. LTD. 2017, PHASE III, GIDC INDUSTRIAL ESTATE, VATVA , AHMEDABAD - 382 445, INDIA. TEL.: (079) 2583 1404, 2583 6320. E MAIL: bdm3@triveniequipments.com Contact : Satyaprakash Shukla (9978876151)</div>			
RFQ No : RA/TEPL/0222/007		Date : 09.02.2022					
1. PRICE BASE : FOR Gandhidham				5,TRANSIT INSURANCE : To Client's Account			
2. P & F : Included				6. Payment : 50% Payment along with PO & Balance 50% payment against PI prior to dispatch.			
3. Freight : Included				7. Validity : 1 Week from offer date			
4. DEL. PERIOD : 10 Weeks from the date of drawing approval.							
SR No.	DESCRIPTION			SIZE	QTY. No.	Unit Rate Rs.	Total Amount Rs.
1	CS Inline Basket Strainer Flanged End ASA 150# RF - Serrated, Construction : Fabricated, Bolted cover & removeable screen arrangement. Dimensions and construction will be as per attached Inquiry Drawing. Hydro Test 5 kg/cm2. MOC : 1a, Shell Pipes : IS 2062 Gr. B - 4mm Thk 1b, Noz. Pipes : IS 2062 Gr. B - 4mm Thk 2a, Shell Flanges : IS 2062 Gr. B Mfg. Std. SORF + BLRF Flanges - 16mm Thk 2b, End Flanges : IS 2062 Gr. B Std. SORF ASA 150# Flanges 3, Screen : SS 304 3mm Dia Hole Perforation 4, Gasket : Synthetic Fibre 5, CL. Studs & Nuts : Steel 6, Drain Valve : CS A 105 1" BSPT (F) Ball Valve 7, Vent Plug : CS A 105 1/4" BSPT (F) 8, Leg Support : CS			DN150 x 150#	1	31415	31,415.00
2	SS 304 Inline Basket Strainer Flanged End ASA 150# RF - Serrated, Construction : Fabricated, Bolted cover & removeable screen arrangement. Dimensions and construction will be as per attached Inquiry Drawing. Hydro Test 5 kg/cm2. MOC : 1a, Shell Pipes : A 240 TP 304 - 4mm Thk 1b, Noz. Pipes : A 240 TP 304 - 4mm Thk 2a, Shell Flanges : A 240 TP 304 Mfg. Std. SORF + BLRF Flange - 14mm Thk 2b, End Flanges : A 240 TP 304 Std. SORF ASA 150# Flanges 3, Screen : SS 304 14 Mesh + 5mm Dia Hole Perforation 4, Gasket : Synthetic Fibre - 3mm Thk 5, CL. Studs & Nuts : A 193 Gr. B7 & A 194 Gr. 2H 6, Drain Valve : SS 304 1" BSPT (F) Ball Valve 7, Vent Plug : SS 304 1/4" BSPT (F) 8, Leg Support : CS			DN300 x 150#	1	211150	211,150.00
Note: We offer following supplementary tests at an Extra Cost. LPT, Radiography of Weld Joint / Casting, IGC Pr. 'E', PMI etc... INSPECTION : TRIVENI / TPIA / CLIENT at our works at no extra cost. WE SHALL FURNISH WORKS TEST CERTIFICATE WITH 10204 3.1 CERTIFICATION.				Sub Total 1 Rs.		242,565.00	
				Discount : 0.00%		-	
				SUB Total- 2 Rs.		242565.00	
				Add P&F Charges Included		0.00	
				Add Freight Chages Rs. Included		0.00	
				SUB Total- 3 Rs.		242565.00	
				Add SGST 9%		21830.85	
				Add CGST 9%		21830.85	
				ADD IGST(OS Sales) 0%		0.00	
GSTIN: 24AAACT7171L1Z4				Prepared Quoted			
				Prashant VAP		GRAND TOTAL Rs.	
						286226.70	
CONDITIONS FOR ABOVE OFFER : 0 Price quoted are based on present Raw material rates. It will change without prior notice. 0 Delivery Period quoted by us is Subject to force mejure.				FOR TRIVENI EQUIPMENTS PVT. LTD. SATYAPRAKASH SHUKLA			